J/70 BUILDING SPECIFICATION

	Specification Description	Minimum	Actual	Maximum	Permitted Modification and/or Dimension Reference and/or Notes
	DECK, HARDWARE AND FITTINGS				
1	FRP Composite deck				Builder supplied and located.
2	Indeck furler unit				Builder supplied and located.
3	Bow "U" bolt mooring eye (stainless)				Builder supplied and located.
4	Shroud chainplates (stainless)				Builder supplied and located.
5	Foredeck opening hatch				Builder supplied (BSI Moonlight).
6	Two anodized jib T-tracks		500m x 25mm		Builder supplied and located. Option to increase number of adjustment holes.
7	Two jib sheet cars				Pull-pin or screw pin. Option to use cars supplied or specified by any licensed builder.
8	Two jib sheet car blocks	40mm			Sheave diameter
9	One pad-eye forward and outboard of each primary winch for connecting jib sheet turning blocks				Builder supplied and located.
10	Two jib sheet turning blocks (ratcheting)			60mm	Option to replace ratcheting blocks with auto-ratcheting blocks.
11	Two jib clew blocks (sailmaker or owner provided)	29mm		40mm	Option to add attaching strop. Ferrules may be used in lieu of blocks.
12	Two 38mm cam cleats, each located near jib sheet turning blocks and cleating inboard.				Builder supplied and located. Cam cleat dimension (38mm) refers to distance between fasteners. 38mm is equivalent to Harken #150 cam cleat.
13	Boomvang - two 38mm fixed cam cleats (USA) or two 29mm swivel cams* (France) at aft corner (P&S) of cabin top				Builder located. Option to add two 29mm deck mounted cheek blocks outboard and forward of hatch lid to deflect the boomvang tails around the hatch. *Equivalent to the Ronstan RF67 or Holt A4867. Risers/wedges may be added to cleats when 29mm deck mounted cheek blocks are fittled.
14	Boomvang large block (where 2:1 passes)				
15	Boomvang smaller blocks (for cascade purchase)	29mm			
15b	Boomvang strop				
16	Two primary winches mounted in standard builder location with two 38mm cam cleats on vertical cockpit sides				Builder supplied and located. Option to replace winches with those supplied or specified by any licensed builder. Option to include winch handle adapter for Harken SnubbAir.
17	One winch handle (optional)				Option for additional winch handles
19	Tack line 38mm cam cleat with fairlead mounted on starboard side of cabin house.				Builder located.
20	Mainsheet traveler track with car, and in line 27mm cam cleats and turning blocks mounted port and starboard on vertical cockpit wall.				Builder supplied and located. Car is Harken 2731 or 2735 or their equivalents.
21	Mainsheet system with swivel arm, block and 38mm cam cleat assembly mounted aft of traveler; lower block mounted on traveler car and upper block connected by strop to the boom.				Builder located.
21a	Main sheet strop connecting fiddle block to boom	434mm		504mm	Builder located. Measured dimension is from bottom surface of boom to the bearing surface of the fiddle block.
22	Mainsheet base block - ratchet	57mm			Option to replace ratcheting block with auto-ratcheting block.
23	Mainsheet fiddle blocks	57mm/40mm			
24	Backstay adjuster hardware of two 27mm cam cleats and four feed blocks.				Builder located.
25	Bow sprit launch line, dead-ended at aft end of sprit, led forward to a block or padeye mounted on forepeak bulkhead, then aft to a thru-deck ferrule (back of strb cabin top) and cleated to a 38mm cam on aft vertical face of cabin.	29mm			Builder located. Dimension is turning block.
25a	Bowsprit bearing inserted into bowsprit opening at forward end of hull for bowsprit to slide through.				Builder supplied and located.
26	Furler line system of two fairleads under deck and one 38mm cam cleat with fairlead mounted on port side of cabin house.				Builder located.
27	Four stainless stanchions with bases with single cockpit safety line. Safety lines secured to stern rail with lashing, and to foredeck stainless eye with lashing or shackle.	305mm			Builder supplied and located. Dimension is safety line height above sheerline. Safety line is 1x19 wire with minimum diameter of 3mm.
28	Two stern pushpits connect with a single safety line.	305mm			Builder supplied and located. Height above sheerline. Safety line is 1x19 wire with minimum diameter of 3mm.
29	GRP molded seahood with hinges, underside padeye and connection hasp for vertical dropboard.				Builder supplied and installed.
30	One plexiglass companionway dropboard capable of being secured or locked from belowdecks.				Builder supplied
31	GRP molded cockpit cover with latch for keel area.				Builder supplied
32	Two heavy duty boat lift pad-eyes installed adjacent to keel (P&S)				Builder supplied
33	Removable, stainless keel safety plate with two heavy duty thru-deck fasteners.				Builder supplied. Option to add removable spacer between top surface of keel and safety plate.
34	Three inspection ports mounted in aft area of cockpit.				Builder supplied and located.
	Gennaker sheet system with four blocks (two may be ratcheting) and two 150 cam cleats. Two forward blocks attach to the mid-cockpit stanchion bases. The two aft blocks attach to the	40mm			Stainless U shackles may be replaced by soft shackles of similar length. Option to attach forward gennaker blocks to the jib block pad-eyes in lieu of mid-cockpit stanchion bases. Option to replace ratcheting blocks with auto-ratcheting
35	pushpit bases.				blocks.
35	pushpit bases. Two aft gennaker sheet blocks	40mm		57mm	

J/70 BUILDING SPECIFICATION

	Specification Description	Minimum	Actual	Maximum	Permitted Modification and/or Dimension Reference and/or Notes
38	One cockpit operated manual bilge pump (French boats)				Optional equipment on USA built boats
39	Two Backstay stainless attachment plates				Builder supplied
40	Fixed, aluminum outboard bracket				Builder supplied and installed.
	HULL AND APPENDAGES				
41	FRP Composite hull				Builder supplied.
42	Keel				Builder supplied. Option for builder provided and installed weed cutter.
43	Keel wedges				Builder supplied and located. No modification of wedges permitted except as in CR E.2.2(c).
44	Rudder				Builder supplied.
44a	Composite tiller				Builder supplied.
45	One tiller extension			1120mm	Option to relocate tiller extension closer to end of tiller.
46	Stainless rudder gudgeons, straps and pins.				Builder supplied and located. Option to use single or double rudder pins. Option to replace with hardware from any licensed J/70 manufacturers.
	SPARS				
47	Mast and boom in carbon fiber with either painted or clearcoat finish.				Builder supplied or specified. Builder located. Option to replace mast base with base supplied or specified by any licensed builder.
48	Single set of spreaders and brackets				Builder supplied and located. Option to extend spreader as approved by manufacturer to match current length specification.
49	Mast base				Builder supplied or specified. Builder located. Option to replace mast base with base supplied or specified by any licensed builder.
50	Boomvang fitting on mast and boom			ļ	Builder supplied and located.
51	Gooseneck fitting on mast and boom				Builder supplied and located.
52	Two stainless padeyes/eye straps (P&S) just above deck level.				Builder supplied and located.
53	Spinnaker halyard swivel cam cleat.	27mm		40mm	Dimension is sheave. Option to add a carabiner clip to underside of boom (to an existing fitting) for running the spinnaker halyard tail.
54	Two part Jib halyard - upper halyard with two loop end terminations (one for furler connection	27mm		40mm	Dimension is sheave. Option to side mount 40mm block with becket on mast or free float with strop.
	and one for connection to lower 4:1 jib halyard fine-tune secured to a swivel cam cleat.)				
55	Main halyard cleat - horn cleat				Builder supplied.
56	Boom end fittings				Builder supplied.
57	Mainsheet attachment fitting				Builder supplied and located.
58	Reefing provision				Builder supplied
59	Cunningham cleat of either a fixed 27mm swivel cam with becket or floating cam cleat assembly.				
60	Carbon fiber bow sprit in either clearcoat or painted finish with stainless U bolt fitting for bowsprit end with integral high load ferrule.				Builder supplied.
<u> </u>	STANDING RIGGING			1	
61	1x19 Stainless wire standing rigging			<u> </u>	
62	Forestay	5mm		ł	Option to replace top forestay swivel with Harken model 207HP.
63	Upper Shrouds	5mm		<u> </u>	
64	Lower shrouds	5mm		1	
65	Upper backstay (Dyneema)	5mm		1	
66	Lower backstay (Dyneema)	5mm			
67	Open body turnbuckles for all shrouds	3		1	
68	Open body turnbuckle in forestay				
69	Backstay legs attached to transom fittings with lashing or shackles (soft or stainless).				
70	{blank}			1	
70	{blank}				
72	{blank}			1	
73	{blank}			1	
74	{blank}				
75	{blank}				
76	{blank}			1	
77	{blank}			ł	
78	{blank}			<u> </u>	
79	{blank}			1	
75	[ound]	L		1	

	Specification Description	Minimum	Actual	Maximum	Permitted Modification and/or Dimension Reference and/or Notes
80	{blank}				
81	{blank}				
	INTERIOR				
82	Molded seats (2)				Builder supplied and located.
83	Aluminum compression post from deck to hull				Builder supplied and located.
84	V-berth molded forward platform with inspection port.				Builder supplied and located.
85	Molded step				Builder supplied and located.
86	Inspection port in aft bulkhead				Option to add drain plug and/or access hatch.
87	GRP cockpit compression post aft of aft bulkhead				Builder supplied and located.
	CHANGELOG — (from 2019-01-01 forward)	Date	Line #		Change
		2022-10-05	54	Deleted "4:1" re	ference to jib halyard fine tune in favor of CR F.4.2. Clarified 40mm max block sheave diameter.
		2022-02-15	3	Deleted "Option docking purpos	n for one 6" (152mm) mooring cleat in lieu of eye , and for other fittings in the bow area if used only for mooring and es."
		2022-02-15	5	Deleted "Option	n to use extra gasket/elastic chord as a preventer (from catching sheets)."
		2022-02-15	12b	Deleted in favor of CR C.7.2(b)(5).	
		2022-02-15	18	Deleted in favor of CR C.7.2(b)(1).	
		2022-02-15	25	Deleted "Option to add an intermediary fairlead on the main bulkhead. Option to rig a retraction system with elastic cord and block	
		2022-02-15	41	Deleted "The center line seam of hull (forward and aft of the keel trunk), within 100mm of either side of centerline, may be smoothene by sanding and/or polishing provided the as-molded shape of the hull is not altered."	
		2022-02-15	47	Deleted "Spars may be repainted or recoated. Option to add a fiberglass backstay flicker to the mast crane."	
		2022-02-15	69	Deleted "Option to add ferrule and lashing to one leg in lieu of standard coarse adjustment."	
		2022-02-15	71-81	Deleted in favor of CR F.4.2	
		2021-01-20	62	Added "Option to replace top forestay swivel with Harken model 207HP."	
		2021-01-20	77b	Deleted in favor of CR C.9.1(l)	
		2021-01-20	89	Deleted in favor of CR C.7.2(b)(6)	
		2020-01-15	21a	Changed dimensional range and measurement points.	
		2020-01-15	27	Deleted "Use of Dyneema permitted only until July 1, 2018. Option to add comfort pads. Option to replace aft lashing with turnbuck or pelican hook."	
		2020-01-15	28	Deleted "Use of Dyneema permitted only until July 1, 2018. Option to add comfort pads. Option to replace aft lashing with turnbuckl or pelican hook."	
		2020-01-15	42a	Deleted in favor of CR C.8.1(f)	
		2020-01-15	43	Added "except as in CR E.2.2(c)."	
		2020-01-15	44	Deleted "Trailing	g edge may be lightly blocked to "square" off."
		2020-01-15	45	Deleted "Option	n to carry spares."

FFFF	CTIVE	15 FEB	RIIARY	2022
LEFE	CIIVL	T 2 L L DI	NUANT	2022

Specification Description	Minimum	Actual	Maximum	Permitted Modification and/or Dimension Reference and/or Notes
	2020-01-15	47	Deleted "Option to replace mast and boom (set only) with those supplied or specified by any licensed builder no more often than o every 12 months."	
	2020-01-15	60	Deleted "Option to add a batten (not to exceed 150mm) to end of sprit to act as a gennaker sheet preventer."	
	2020-01-15	66	Deleted "Option to add elastic chord to take up slack on the backstay bridle." in favor of CR 9.1	
	2020-01-15	70	Deleted in favor	of CR C.7.2(b)
	2020-01-15	77b	Added "(optiona)"; deleted "Lanyard no longer than needed to provide purchase."
	2020-01-15	88	Deleted in favor	of CR C.7.2(b)(7)
	2019-04-18	47	Added "or specif	ed."
	2019-04-18	47	Added "Option to every 12 months	o replace mast and boom (set only) with those supplied or specified by any licensed builder no more often than once ."
	2019-04-18	49	Added "or specif	ed."
	2019-04-18	49	Added "Builder l	ocated. Option to replace mast base with base supplied or specified by any licensed builder."
	2019-02-25	16	Added "Option t	o include winch handle adapter for Harken SnubbAir."
	2019-02-25	17	Added "(optiona)"
	2019-02-25	17	Deleted "200mm	"